BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

ame of Work :- Reserve fund for Emergency works in Bagalagunte Ward No.14, T. asarahalli Sub Division.

						Est. Cost Rs	20.00	Lakhs

Description of item	Unit	No	L	B	D	Qty	Rate	Amount
Providing, laying, spreading and compacting graded stone aggregates to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. Specification No. 406 with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.(PWD SR 2016-17, P.No.155 I No.20.18)								
Bhuvaneshwari Nagara road	Sqm Cum	3	3.00	3.00	0.20	27.00		
Manjunatha Nagara Main road		2	2.80	2.80	0.20	15.68		
Manjunatha Nagara Coconut Garden, 7th Main		2	2.00	3.00	0.20	12.00		
Muneshwara Nagara Main road		4	3.00	3.00	0.20	36.00		
Difence colony road		5	3.00	3.00	0.20	45.00		
		4	2.30	2.60	0.20	23.92		
Vinayaka Nagara road		9	2.40	3.00	0.20	64.80		
		4	2.50	2.50	0.20	25.00		
Bagalagunte Village road		8	2.00	3.00	0.20	48.00		
Bad Reaches								
Sidedahalli Main road		4	15.00	4.50	0.20	270.00		
Soundarya Layout cross roads		5	5.00	5.00	0.20	125.00		
						692.40	2001.28	1385686.00

1858.00
133.28
2021.28

Description of item	Unit	No	L	B	D	Qty	Rate	Amount
Basic Rate	1888.00							
Add Area Weightage 6%	113.28							
Total	2001.28							
KSRRB 3000 Filling Pot-holes and Patch Repairs with Bituminous Concrete, 40 mm KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, applying tack coat on the sides and base of excavation at 2.5kg/10sqm as per clause 500.3, filling back the pot holes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 including cost of materials, labour, HOM complete as per specifications. MORTH Specification No. 3004.2 It.No 35.5 P- PWD SR 2018-19								
Bhuvaneshwari Nagara road	Sqm	3	3.00	3.00		27.00		
Manjunatha Nagara Main road		2	2.80	2.80		15.68		
Manjunatha Nagara Coconut Garden, 7th Main		2	2.00	3.00		12.00		
Muneshwara Nagara Main road		4	3.00	3.00		36.00		
Difence colony road		5	3.00	3.00		45.00		
		4	2.30	2.60		23.92		
Vinayaka Nagara road		9	2.40	3.00		64.80		
		4	2.50	2.50		25.00		
Bagalagunte Village road		8	2.00	3.00		48.00		
Bad Reaches						0.00		
Sidedahalli Main road		4	15.00	4.50		270.00		
Soundarya Layout cross roads		5	5.00	5.00		125.00		
						692.40	365.70	253211.00
Basic Rate	345.00							
Add Area Weightage 6%	20.70							
Total	365.70							

307.00
18.42
325.42

Description of item	Unit	No	L	B	D	Qty	Rate	Amount
						Sub Total		1638470.00
Tender Premium Charge 5%								100000.00
PMC Charge 1%								20000.00
GST Charge 12%								240000.00
Miscellaneous and UnforessenCharges								1530.00
							Total	2000000.00
(Rupees Twenty Lakhs Only)								

Assistant Engineer
Ward-14

Assistant Executive Engineer
T. Dasarahalli Sub-Division
B.B.M.P

Executive Engineer
Dasarahalli Division
B.B.M.P. Bangalore.

ನಂ. EE/DD/AS/77/ದಿನಾಂಕ: 18/12/19
ರೂ. ಇಪ್ಪತ್ತು ಲಕ್ಷಗಳು ಮಾತ್ರ
ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.

ನಂ. EE/DD/TS/13/ದಿನಾಂಕ: 18/12/19
ರೂ. ಇಪ್ಪತ್ತು ಲಕ್ಷಗಳು ಮಾತ್ರ
ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ವಲಯ,